

IIT Madras Research Park,

No.1FA, First floor, Kanagam road, Taramani, Chennai. 600113. Ph. 044-66469800.

Notice Inviting Quotation.

Sealed item rate quotations are invited by the undersigned on behalf of IITMRP from the contactors to carry out the following work. The quotations shall reach this office at the above mentioned address on or before **5PM of 30-08-2019**

The undersigned reserve the right to accept or reject whole or part of the quotations without assigning any reason thereof.

The rate shall be quoted only in the format of BOQ attached with this quotation

Name of work: Revamping of Access ladder & platform in shafts of Phase-I Building

Time limit to carry out the work: Ten days which shall be counted after 5 days from the date of issue of Work order

SCHEDULE OF QUANTITIES

Sl No	Item Description	Unit	Quantity	Rate in words and figures	Amount
1.	Providing and Fixing MS ladder made of L-angle 50x50x6 mm outer frame , 50x25x3mm tube steps and up to 600mm width of required length cost including one coat steel primer. The work includes cutting, welding, grinding etc. for duct work height upto 54m	Rm	205.00		
2.	Providing and Fixing MS Flat of size 40x40x6 mm required length for soft inside platform including one coat steel primer ,for duct work height upto 54m	Rm	2103.00		
3.	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. for duct work height upto 54m (ISMC-100mmx50mmx6mm)	Kg	4200.00		
4.	Providing and fixing 16mm dia Hilt fasters (HSV M16X140) to the existing RCC beam& slab as per Hilty Specification including drilling , filling materials, chemicals & necessary fixtures etc duct work height upto 54m	Nos	450.00		
5.	Supply and painting for duct work . Work involves cleaning the existing surface and 2 coats of Epoxy paint of approved brand over a existing surface , Lifeline & Safety accessories for the labourers all complete.	Sqm	811.00		

6.	Providing and fixing double scaffolding in E block plumbing shaft , up to a height of 54m made with 90mm dia. casuarinas post centre to centre horizontal and vertical joining with coir in the scaffolding for working platform etc., and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc., for a length up to 3.5m	Rm	330.00		
7.	Removing of Structural steels such as channels, MS ladder and MS Flat, bolted or welded steel sections. and removing scrap materials out side the IITMRP campus	Kg	12600.00		
	Total (in figures and words.)				

C.O.O
For IITMRP.

To
All the vendors as per mailing list.
WEB-SITE of IITMRP.

Notes for bidders:

1. The bidder shall visit the site and understand the site conditions clearly.
2. All measurements shall be taken at site.
3. Payment shall be made only for the quantity fixed at site.
4. Work shall be started 5days after issues of work order/purchase order and shall be completed 60days from the date of start.
5. The work shall be carried out in co-ordination with M/s. AFM/OCS teams.
6. All taxes must be mentioned clearly
7. Payment will be made with 30days of invoice submission
- 8.All safety measures should taken at your scope
- 9.Scaffolding is at your scope.

Address and signature of contractor

